ENGINEERING DEPARTMENT.

CHITALDRUG DIVISION.

Dated 2nd June 1919.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 20th June 1919, for improving the Godabanahal Hannehal tank, Registered No. 38, Chitaldrug Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1920.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug, between the hours of 11 A.M. and 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 (two hundred) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving the Godabanahal Hannehal tank, Registered No. 38, Chitaldrug Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for improving Godabanahal Honnehal tank, Registered No. 38, Chitaldrug Taluk, Chitaldrug District:—

Serial No.	Items of work	Per	Total quantity
	Bund R. L. 108·00 *top width* 5′ *slope* 1½ : 1.		
1	Earthwork to bund including watering and tamping cutting grips and forming good joints to the base thoroughly cleared.	C. yd.	9,032
2	Removing the apron of right weir and utilising the same for revetment in front	Lump sum	
		C. yd.	50
3	Turfing with mani grass	S. yd.	7,070
4	Removing the old revetment and utilising the same to road embankment	C. yd.	260
5	New stone revetment with lead, etc.	C. yd.	1,180
6	Removing and refixing grade stones with bed slabs including painting	Each	37
7	Providing new grade stones with bed slabs	"	3
8	Removing and refixing top width stones	"	37
9	New bed grade stones	"	3
10	Removing and refixing registered number stone including painting	"	1
11	Do and refixing gauge stones and painting	"	1
12	Do and B. M. stones to be fixed higher up	"	2
13	Providing date stone	"	1
14	Removing the right weir aprons and connected old and new bund with required sections.	Lump sum	Rs.
	Old sluice R. L. 91·22 (*Sill*).		
15	Marking gauge on the gibbet stone with cement and raising the gibbet by 3 feet R. L. 102·00, 1½′ wall with burnt brick in surki mortar and cement plastering with burnt stone slabs, coping and looking arrangements to the plug rod and clearing site in front of sluice.	Lump sum	Rs.
	Waste weir left 175 *feet long R. L.* 102·00.		
16	Earthwork excavation and utilising the earth to ring bund, etc.	C. yd.	315
17	Filling in foundation with surki concrete	C. ft.	2,096
18	Burnt brick in surki mortar	"	1,600
19	Burnt stone slabs 6″ thick with joints, etc., complete	S. ft.	447
20	Plastering with nice surki mortar including watering, etc., complete	Sq.	10·35
21	Rough plastering with surki mortar to toe wall wherever necessary	"	6·00
22	Rough stone apron with jelly and lead, etc.	C. yd.	390
23	Cement pointing to the joints of coping slabs of body wall and toe wall	Sq.	6·00
24	Cutting ramps to pass carts over the bund as usual behind the proposed jack bund and weir crossings.	Lump sum	Rs.
25	Compensation for lands	Acre	21½

B. VENKATADASAPPA,
For *Executive Engineer.*